



GOVERNMENT OF TELANGANA

MISSION BHAGIRATHA DEPARTMENT



ఇంటింటికీ కాగునీరు, ఇల్లాలి కష్టాలు లేరు



Foundation laid by Hon'ble CM at Choutuppal
on 08.06.2015




Hon'ble PM commissioned Gajwel scheme
on 07.08.2016

Piped Water Supply to All – Mission Bhagiratha



TELANGANA- At a Glance



Districts	32
Mandals	540
Gram Panchayats	12,755
Villages	10,472
Rural Habitations	24,042
SC Dominated Habitations	1700
ST Dominated Habitations	9823
Rural Population (Lakhs)	208.71
SC Population(Lakhs)	39.24
ST Population (Lakhs)	29.78



Need of 'Mission Bhagiratha'



➤ Infrastructure and supply (Before Mission)

- Single Village Schemes (PWS) : 17,340
- Multi Village Schemes (CPWSS) : 168
- Only 33 % households have tap connections



➤ Quality Issues/Chronic drought conditions-scarcity of drinking water

- Every alternative year, the state is facing drought situation.
- Deficit rainfall in 6 years during last decade.
- Due to over exploitation, the ground water table depleted and quality effected
- Depletion of Ground water – by more than 2 metres in last 10 years
- 82% Drinking water Schemes dependent on Ground Water sources
- Water quality issues-excess fluoride(1043 habs),nitrates(163 habs),TDS(187 habs)
- Transportation to about 15% habitations in Summer

➤ Productivity loss due to time spent on fetching water

➤ Loss of human lives due to water borne diseases

➤ GOI (NRDWP guidelines) – to shift from Ground water to perennial surface sources





Objective



- ❖ To supply surface treated water to all the rural habitations and Urban Local Bodies other than GHMC and its surrounding habitations within ORR


- ❖ Per Capita Supply
 - ✓ 100 LPCD (litres per capita per day) for rural areas
 - ✓ 135 LPCD for Municipalities
 - ✓ 150 LPCD for Municipal Corporations

- ❖ Up to 10 % of the total designed demand is proposed for Bulk Supply to Industries/Institutes/ Commercial Establishments

- ❖ To provide free household tap connection to each household in all the rural habitations.



MISSION BHAGIRATHA PROJECT TELANGANA




Legend

STRUCTURES

- BPT
- GLBR
- OHBR
- PHOUSE
- SUMP
- ★ DISTRICT HEADQUARTERS
- ★ MUNICIPALITIES
- INTAKE WELL
- WATER TREATMENT PLANT
- RESERVOIRS
- OUTER RINGROAD
- BOUNDARY

COVERAGE UNDER KRISHNA AND GODAVARI RIVER BASINS



-  Intake Well
-  WTP




Mission Bhagiratha- Planning



- ❖ The project is divided into 26 major segments/34 sub segments based on the topography and proximity/availability of raw water from the source to cover the rural habitations and ULBs within the boundary.
- ❖ All Raw Water Sources for the 26 Major Segments/34 Sub Segments were identified and quantum water to be drawn from each source
- ❖ Necessary permissions from the I&CAD department were obtained for drawl of raw water from the identified sources.
- ❖ Location of WTPs were indentified and transmission network was planned based on the detailed survey duly integrating the feasible existing infrastructure
- ❖ In village infrastructure requirement like OHSRs, Distribution pipelines and household connections were planned in phased manner duly integrating the existing infrastructure
- ❖ Estimates are prepared in phased manner and proposals submitted to the Government for administrative sanction.

MISSION BHAGIRATHA PROJECT-TELANGANA

26 Segments





PRINICIPLE OF DESIGN



It is an *end-to-end design solution*, planned to meet all requirements up to 2048. It relies on treating surface water from major rivers, **Godavari** (53 tmc) and **Krishna** (32 tmc). For all the surface water bodies a reserve is maintained, for drinking water purpose, by fixing **MINIMUM DRAW DOWN LEVELS (MDDL)** and monitored regularly. The fundamental principle inbuilt into its design, is that *water is to be conveyed by gravity(98%)*, reducing the capex & maintenance cost to lift pumps.



STAGES TO REACH HOUSEHOLD



Main stages involved are:

- ✓ Sourcing water, through **Intake Wells**, from major rivers or reservoirs fed by these rivers
- ✓ Purifying the raw water in nearby **Water Treatment Plant (WTP)**
- ✓ Pump treated water to **Over Head Balancing Reservoirs (OHBRs)** at the highest points
- ✓ Transmit from highest point through **secondary pipeline network** to all the OHBRs located in habitations by gravity
- ✓ Distribute to each household through a modern, rationalized intra village network by providing **tap connection to each household**

Typical methodology





STRATEGY



State Initiatives



- ❖ Government intention of water supply to each household was declared during September 2014 in a meeting
- ❖ Series of meetings were conducted at planning stage of the schemes during 2014 & 2015
- ❖ General guidelines for the project was issued from time to time based on the meetings conducted by Chief Secretary, Hon'ble CM and Hon'ble Ministers
- ❖ Telangana Drinking Water Supply Corporation Limited (TDWSCL) formed under the chairmanship of Hon'ble CM during February 2015.
- ❖ The department was reorganized during February 2015 duly sanctioning 1718 Additional posts to implement the project.
- ❖ Right of User (RoU) Act brought in for laying of pipelines in Private land during Feb 2015
- ❖ WAPCOS was engaged as third party quality control and monitoring Consultant for Grid works



Hon'ble Chief Minister of Telangana Addressing All Water Supply Engineers on Govt. Vision on 10.09.2014





INSTITUTIONAL SETUP



- ❖ Mission Bhagiratha declared as Flagship programme
- ❖ Effective **coordination mechanism** put in place at both State and district levels.
- ❖ **Separate wings** were created within the department i.e 1) Bulk Supply and 2) Intra Village works 3) V&QC
- ❖ Retired Chief Engineers/Superintending Engineers, District Forest Officers were engaged for **utilising** their **expertise** in the field
- ❖ Experts within the department were identified and **developed GIS/MIS websites**
- ❖ Regular Trainings were given to the staff to adopt new techniques like utilizing **new software** EPANET, WATERGEMS, KY-PIPE etc and also in modern survey equipment
- ❖ MoU with NIC, Telangana for **development of web GIS** application



MEETING WITH MANUFACTURERS

24.10.2014






DGPS /TOTAL STATION - TRAINING



DGPS Survey training at Karimnagar



Total Station Survey training at Medak





TRAINING TO AEEs/AEs





Critical Items & Bottle necks



- Critical items were identified in the project which will take more time were started in the 1st instance such as Intake Wells and WTPs
- Land acquisition was done much in advance and majority part government land were used
- Joint coordination meetings were conducted at highest level in the planning stage of the project to sort out the issues related to forest clearances, railway track crossings, Right of way along the National Highways , State High Ways, Local Roads
- Right of User (RoU) Act brought for laying of pipelines in Private Land

❖ Service crossings (Total) - 13901 Nos

- Railway crossings 242
- NH crossings 560
- R&B crossings 4526
- PR Road crossings 6953
- Canal crossings 1453
- River/Riverlet crossings 167





Implementation



Administrative Sanctions



- Administrative sanctions were accorded by the Government based on the proposals from the Department from time to time for Grid works and intra village works
- Grid administrative sanctions were accorded (Total Rs.37886.53 Cr) in three phases for certain segments based on the planning
 - ✓ **Phase-1 : Intake structures, Raw water mains, WTPs and pumping system**
 - ✓ **Phase2 : Balance WTPs and entire transmission system**
 - ✓ **Phase-3 : Augmentation of Supply to existing Segments**
- Intra Village administrative sanctions were accorded (Total Rs.8674.07 cr) in several phases, Mandal as a unit for construction of OHSRs, Distribution pipelines and providing household connections
- Separate administrative sanctions were also accorded (Rs. 25.08 Cr) for isolated habitations where the surface water supply is not feasible for construction of solar pumping system, distribution of pipeline and house connections.



FUNDS MOBILIZATION



- For implementing a massive project with huge financial outlay and in order to provide safe and sustainable drinking water to the people of the State in a strict time frame, mobilising the resources outside the budget has become necessary which will not only bring immense social benefits to masses but also avoid any possible cost over run in the project
 - HUDCO Loan
 - NABARD Loan
 - Commercial Banks Loan
 - State Government Budgetary support
 - GOI-NRDWP NWQSM Project



Monitoring Tools



- Divisional level video conference system was established before commencement of the project for review and monitoring on weekly basis
- Mobile Apps, GIS and MIS developed for monitoring the progress and asset management
- Geo tagging of all assets including tap connections with CAN in process
- Monthly review meetings used to be conducted by the Hon'ble CM/Hon'ble Minister/ Chief Secretary during the implementation where the concerned Ses/EEs to present the progress with the latest progress photos



VIDEO CONFERENCE





BEST PRACTICES IN IMPLEMENTATION



- Taken up in **Saturation mode**
- All feasible **existing** infra structure **integrated**
- **Avoiding** usage of non sustainable pipe materials like **GRP and AC**
- **No mobilization advance** to Agencies
- Sick firms were avoided by introducing **CDR clause**
- **Incentives** to the Agencies for early completion
- **Coordination Meetings** with manufacturers before commencement to meet the demand
- **Continuous Funds Flow** maintained for early completion
- Telangana State Remote Sensing Application Centre(TRAC) MAPS were utilised for preparation of preliminary network plans
- DGPS Survey was conducted to save the time for pipeline route
- Software like EPANET/WATER GEMS were utilised for network analysis



FLOW CONTROL VALVE



MDPE Pipe




FCV

Saddle Clamp

Main Pipe Connection



- Flow control valves are being installed with a design flow of 5 LPM at house hold connection point. Flow control valve also disables drawing excess water through pumps by the individuals.
- The required capacity of OHSRs, i.e 50% of the demand, are being constructed duly integrating the existing OHSRs which are in good condition.
- All the estimates are prepared based on Standard Schedule of Rates(SSR) approved by the State Government





RESULTS OF FCVs



Water Reaching up to 1st Floor of the House me flow



Measuring the Flow from Taps



Execution & Commissioning



❖ Grid Infrastructure Created

- ✓ Intake Wells (Nos) - 19
- ✓ WTPs (Nos) - 50
- ✓ Pipeline (KM) - 55,441
- ✓ The 26 Segments/34 Sub Segments are commissioned in phased manner from 2017 till 2022.
- ✓ Total 23,839 habitations and 121 ULBs are being covered with bulk treated water supply.

❖ Intra Village Infrastructure Created

- ✓ OHSR - 19,560
- ✓ Pipeline(KM) - 67,314
- ✓ House Connections - 59.51 lakhs



DEVELOPMENT OF UTILITIES



In a **record-time of 3 years** the TDWSC created the following infrastructure:

❖ Intake wells:

 Total	72
• New	19
• Existing integrated	53

❖ Water Treatment Plants:

		Total Capacity
 Total	121	4,109 MLD
• New	50	3,349 MLD
• Existing integrated	71	760 MLD

❖ OHBRs/BPTs:

		Total Capacity
 Total	897	1,00,730 KL
• New	577	74,540 KL
• Existing integrated	307	26,190 KL



❖ GLBRs:

+ Total

- **New**
- Existing integrated

190

153

42

Total Capacity

1,07,350 KL

96,070 KL

11,280 KL

❖ Sumps:

+ Total

- **New**
- Existing integrated

711

594

200

Total Capacity

9,00,150 KL

7,40,850 KL

1,59,300 KL

❖ Pipelines:

+ Total

- **New**
- Existing integrated

1.50 Lakh Kms

1.12 Lakh Kms

0.38 Lakh Kms



❖ Village OHSRs:

		Total Capacity
 Total	37,002	15,32,690 KL
● New	19,560	7,24,600 KL
● Existing integrated	17,442	8,08,090 KL



❖ Power required:

187 MW

+ HT Connections **164**

- 220 KV 2
- 33 KV 42
- 11 KV 120

+ LT Connections **253**

❖ Pump sets:

Total Capacity

+ Total	1,128	2,48,086 KW
● LT	916	1,71,856 KW
● HT	212	76,230 KW

MISSION BHAGIRATHA PIPELINE NETWORK



Legend

- Structures
- Existing Network
- Prop. Gravity Main
- Prop. Pumping Main
- Water bodies
- Segment_Bdy





INFRASTRUCTURE SUSTAINABILITY



SOURCE SUSTAINABILITY



సంపదించినీ అభివృద్ధి, సాగునీ నీటిని తీసు


- All the Surface water sources selected are **major Reservoirs/Balancing Reservoirs** fed by either Godavari or Krishna River/Canal
- Top priority given for drinking water, **Minimum Draw Down Level (MDDL)** in each reservoir fixed by Govt. based on the annual water requirement.
- Daily water levels are being monitored by Mission Bhagiratha Department
- Majority of the reservoirs interlinked with **Major Lift Irrigation Schemes(Kaleswaram, Palamuru, Seetharama etc.)** to make it more sustainable



Water Treatment



- Rapid Sand Filtration Technology
 - ✓ Operation - 23.5 Hours
 - ✓ Recycling of Back Wash Water - 3 % savings
- Establishing Water Quality Laboratories with adequate manpower
- SCADA System
 - ✓ Monitoring Inflows and outflows of treated water
 - ✓ Automated back wash system
 - ✓ Effective chemical dosing





Pipe Policy



- ❖ The pipe policy for the project has been set based on the CPHEEO Guidelines and local terrain conditions
- ✓ Transmission Lines - Mild Steel, Ductile Iron, BWSCP, PCCP and HDPE
- ✓ Intra-Village Lines - HDPE and PVC





DEFECT LIABILITY



- As part of the contract conditions, the defect liability period for all civil and pipelines is 5 years from the date of commissioning.
- Defect Liability period for the Electro – Mechanical works is 10 years from the date of commissioning.
- The Agency/Contractor who executed the works has to operate & Maintain the infrastructure for 10 years from the date of commissioning.



Quality Control



- Vendor Registration was done to encourage best Manufacturers
- Pre-Delivery inspection was conducted jointly by the representative of the Department, WAPCOS and Agency for all the materials such as pipes, valves, pumps, motors etc.,
- A third party vetting & quality control Agency (WAPCOS) was engaged to submit an independent QC inspection report



SERVICE DELIVERY



- Log sheets signed by the Gram Sarpanch is uploaded online to ensure the bulk supply
- By weekly meetings are conducted to ensure all the service reservoirs/habitations are covered with bulk supply without missing
- Stabilization programme being conducted to ensure all the intra village works are completed to meet the standards
- GP resolution is being obtained for 100% household functionary tap
- Contact No of the concerned Engineers being displayed at GP office to contact for any grievances

MISSION BHAGIRATHA DAILY WATER SUPPLY LOG BOOK

Mandal Name: Devarakadra

Habitation Name:

Bollaram

Population (2011/2020): 1818/1953

Grampanchayat Name: Bollaram

Sarpanch Name:

Laxamma

Cell No: 9849278038

Secretary Name:

Rakeh

Cell No:

9200049595

Date (Sunday to Saturday)	OHSR 1		OHSR 2		OHSR 3		OHSR 4		Waterman	Secretary	Sarpanch	Counter sign by AEE
	Location : Village Entrance		Location : Village Entrance		Location : Village Entrance		Location : SC Colony					
	Capacity in KL:	40	Capacity in KL:	40	Capacity in KL:	10	Capacity in KL:	30				
	No of Households:	139	No of Households:	143	No of Households:	33	No of Households:	111				
	Total demand (KL) under OHSR as per households in KL:	55.60	Total demand (KL) under OHSR as per households in KL:	57.20	Total demand (KL) under OHSR as per households in KL:	13.20	Total demand (KL) under OHSR as per households in KL:	44.40				
1st filling in KL	2nd filling in KL	1st filling in KL	2nd filling in KL	1st filling in KL	2nd filling in KL	1st filling in KL	2nd filling in KL					
<i>13/12</i>	<i>40</i>	<i>20</i>	<i>40</i>	<i>20</i>	<i>10</i>	<i>5</i>	<i>30</i>	<i>15</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>
<i>14/12</i>	<i>40</i>	<i>20</i>	<i>40</i>	<i>20</i>	<i>10</i>	<i>5</i>	<i>30</i>	<i>15</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>
<i>15/12</i>	<i>40</i>	<i>-</i>	<i>40</i>	<i>-</i>	<i>10</i>	<i>-</i>	<i>30</i>	<i>-</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>
<i>16/12</i>	<i>40</i>	<i>20</i>	<i>40</i>	<i>20</i>	<i>10</i>	<i>5</i>	<i>30</i>	<i>15</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>
<i>17/12</i>	<i>40</i>	<i>20</i>	<i>40</i>	<i>20</i>	<i>10</i>	<i>5</i>	<i>30</i>	<i>15</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>
<i>18/12</i>	<i>40</i>	<i>20</i>	<i>40</i>	<i>20</i>	<i>10</i>	<i>5</i>	<i>30</i>	<i>15</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>
<i>19/12</i>	<i>40</i>	<i>20</i>	<i>40</i>	<i>20</i>	<i>10</i>	<i>5</i>	<i>30</i>	<i>15</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>	<i>W2032</i>

ಶಿಬಿರ ವಾಹಿನಿ
ಶಿಬಿರ ವಾಹಿನಿ

[Signature]
DY EXECUTIVE ENGINEER
MB GRID SD MBNR

Verified
by
EXECUTIVE ENGINEER
MB GRID DIVISION MBNR



మండలం, చిన్నరాయపూర్ గ్రామ పంచాయతీ పరిధిలో ఉన్న కనకనమిల్ మిషన్ భగీరథ పనులు పూర్తిచేయడంపై.

1. ఇంటింటి నల్ల కనకనమిల్ పాతవి -----
- కొత్తవి (మిషన్ భగీరథ ద్వారా) 116
- మొత్తం ఇంటింటి నల్ల కనకనమిల్ 116
2. ప్రభుత్వ కార్యాలయాలకు నల్ల కనకనమిల్ -----
3. స్కూళ్లకు నల్ల కనకనమిల్ 01
4. అంగన్వాడీలకు నల్ల కనకనమిల్ 01
5. ప్రభుత్వ ఆరోగ్యకేంద్రములకు నల్ల కనకనమిల్ -----
6. ప్రాథమిక ఆరోగ్య కేంద్రాలకు నల్ల కనకనమిల్ -----
7. -----
8. -----

మొత్తం నల్ల కనకనమిల్ 118

కావున మొత్తం మా గ్రామములో 118 నల్ల కనకనమిల్ కలవు. మరియు మా గ్రామ పరిధిలో ఏ ఒక్క ఇంటికి కూడా నల్ల కనకనమిల్ మిగిలి లేదు. కావున దృవీకరించడంపై.

K. అమృత
సర్పంచ్
గ్రామం: చిన్నరాయపూర్
మండలం: చెన్నూర్.

GP RESOLUTION

This is to resolve that the Mission Bhagiratha works are completed In Narayanapur Habitation of Narayanapur Gram Panchayath, Chennur Mandal, Mancherla district

1. Household Connections given:
 - i. Existing Household Connections : 0
 - ii. New Household Connections : 116
 - Total Household Connections : 116
2. Government Office/Buildings : 0
3. Schools : 1
4. Anganwadis : 1
5. Government Hospitals/PHCs : 0
6. Religious Places : 0

Total Tap Connections : 118

Thus, in Narayanpur Habitation, there are 118 household tap connections and there are no balance left over households without tap connections. Hence the same is certified.

**Signature of Sarpanch
with GP seal**



Dr. Sunil.KR.BARNWAL, Secretary to CM, Jarkhand tastes MB tap water at Gajwel during Dec 2019



Sri. Ravi Kanth, HUDCO CMD Tastes the MB tap Water at Pothireddypallygudem of PAPally(M) during Dec 2019



Dr. Tamilisai Soundararajan, Hon'ble Governor, Telangana - inaugurating tap at Mulugu





O&M WORKSHOPS





COMMUNITY INVOLVEMENT



- Trainings were imparted to Gram Sarpanches, village secretaries, Anganwadi Workers and village Watermen
- Awareness programme being organised at WTP level involving public representatives and village watermen to explain about quality of water being produced.
- Health hazards of consuming R.O water is explained as part of trainings and awareness programme



WORKSHOPS at Village Level



Warangal (U)



Medak



Mahabubnagar



Suryapet



By Sri. Y. Dayaker Rao, Hon'ble Minister ,PR&RD



Mahabubabad



BADRADRI-KOTHAGUDEM





AWARENESS CAMPS



Bommarasipet(M)



Jagitiyal(M)



Darmasagar(M)



Peddapally (M)



AWARENESS CAMPS



BADRADRI-KOTHAGUDEM

ADILABAD





AWARENESS CAMPS



Kuppanagar(V), Jarasangam(M), Sangareddy

Kothamalgora(V), Mahabubnagar



Nerodigonda (V), Yapalguda(M), Adilabad

Govindpur (V), Bheempur (M), Adilabad



AWARENESS CAMPS



At ZP Meeting, Khmmam



Nargudem (V), Kattangur(M), Nalgonda



Adraspally (V), MC Pally(M), Medchal



Revulapally (V), Shankerpally(M), RR



Jal Jeevan Mission -Har Ghar Jal



- Jal Jeevan Mission(JJM) has been launched by GOI, to enable every household in villages to have Functional Household Tap Connection(FHTC) by 2024
- Operational Guidelines were issued in December 2019
- Supply to Houses – 55 lpcd (Surface Water/Ground Water)
- Funding : Central 50% and State 50% other than Himalayan, North Eastern States and Union Territories



Intake wells



Palair segment



55m x 12m x 14m Intake well



Singur Reservoir capacity: 29.61 TMC ;
Annual requirement: 1.88 TMC
Habs covered: 873

30m x 12m Intake well at Singur reservoir near Peddareddipet



Yellore Segment

130.25 x 36m Intake Well at Yellore



Srisailem capacity: 215.8 TMC ; Dead storage : 53.85 TMC
Annual requirement: 9 TMC ; Habs covered: 4469 (3088 MBNR+1381 RR)





Yellore Segment

130.25 x 36m Intake Well at Yellore



Srisaigram capacity: 215.8 TMC ; Dead storage : 53.85 TMC
Annual requirement: 9 TMC ; Habs covered: 4469 (3088 MBNR+1381 RR)





Yellore Segment





Intake well @ Chali vagu



8m dia Intake at Godavari Pusuru (Wazeedu mandal)



Wyra segment – Khammam Dist



Intake well @ Wyra Reservoir



Intake at Dummugudem





Treatment Plants



Jurala Segment



70 MLD WTP @ Jurala





Peddapally Ramagundam segment

160 MLD WTP @ Murmur



సాగునీటి అభివృద్ధి, నాణ్యత నిర్ధారణ





Srisailam segment 135 MLD @ Raghavapur





Singur Jukkal Segment



పానబోధ విభాగం, తెలంగాణ ప్రభుత్వం



145 MLD WTP @ Peddareddy pet



LMD MHH Segment



125 MLD WTP @ LMD colony





Palair segment



90 MLD WTP @ Jeellacheruvu





Singur Medak segment

90 MLD WTP at Peddareddipet





Yellore Segment



31 MLD WTP @ Yellore





Structures & Pipelines



HMWSSB Gajwel segment



550 KL & 150 KI OHBRs @Komatibanda

14000 KL GLBR@Komatibanda



HMWSSB -Warangal segment



1800 KL OHBR @ komaravelly



SRSP Adilabad segment





AKBR segment -GLBRs on Gollakonda hillock





LMD Parkal segment -GLBRs on Ramappa hillock





MHH segment -GLBRs on Porandla hillock





Yellore Segment



2.4 mtrs dia MS Pipe line





Yellore Segment





Pumpsets @ Mallannagutta WTP





Srisailam segment



120 KL @ Shabad



1000 KL OHBR @ Rakamcherla



Electrical Sub stations





Railway crossing executed with Horizontal drilling by jack pushing method



Railway crossing @ Vangapally



Canal & Highway crossings





Canal Crossing in Yellore Segment





Intra Village system-OHSRs



OHSR at G+2 Colony



40KL OHSR at Gurralapadu



HMWSSB Gajwel segment





Last mile connectivity at Bhadrachalam tribal areas





Excavation for Pipeline laying in Agriculture fields of Hon'ble CM at Yerravally, Medak dist as per ROU act





Inspection of Bhagiratha Works by H.E Governor and Hon'ble Chief Minister





THANK YOU