



Dr. MCR HUMAN RESOURCE DEVELOPMENT INSTITUTE OF TELANGANA
GOVERNMENT OF TELANGANA
ROAD No. 25, JUBILEE HILLS, HYDERABAD – 500 033

From
The General Manager (E&F)

To
1.
2.
3.

Lr.No.E1/691/2025, Dt/08.08.2026

Sub: Dr.MCR HRDIT, Hyd - Engineering Section- Procurement of
electrical material - Sealed Quotations - Invited -Reg.

&&&

Dr. MCR HRD Institute of Telangana intends to procure certain electrical materials to attend the repairs to non -functioning street lights in the Institute campus. Accordingly, sealed quotations are invited from agencies / contractors / vendors for the supply of plumbing material as per the schedule enclosed.

S.No	Name of work	ECV of work (Rs.)	Period for completion of work	Contractor eligible to apply for tender schedules
1	Procurement of electrical material	2,71,491	7 days	Registered Firms /contractors Minimum – Class-V

Date of quotations submission (hard copy): From 01.08.2026 to 03.08.2026 @ 02.00 pm

Date of opening of quotations: 03.08.2026 at 3.30 pm.

Terms & Conditions:

1. The interested agencies shall inspect the work site and acquaint themselves with the scope and nature of the work before submitting their quotations.
2. The agencies shall furnish details of their previous experience in executing similar works, along with supporting documents, including contractor registration, GST registration, PAN, and other relevant statutory documents, with the sealed quotation.
3. Further information and technical details pertaining to the work may be obtained from the Engineering Wing, Office of the Director General, Dr. MCR HRD Institute, Hyderabad, on any working day during office hours.
4. The detailed schedule of quantities/specifications is enclosed herewith.
5. The General Manager (Engineering & Facilities), Dr.MCR HRD Institute, Hyderabad, reserves the right to accept or reject any or all quotations, wholly or partially, without assigning any reason thereof, and the decision of the Institute shall be final and binding.

6. The quotation shall be submitted in a sealed cover, duly super scribed with the following details:


“Quotation for Procurement of electrical material to the Institute.”

From:

(Name and Address of the Bidder with stamp)

To

The General Manager (E&F),
Dr.MCR HRD Institute of Telangana,
Road No. 25, Jubilee Hills,
Hyderabad – 500033.


General Manager (E&F)

To

The Notice Board at Engg. Wing, 1st floor, Muchukunda Block, Dr.MCR HRDIT,Hyd.
Copy to GM(IT) for uploading the document in the Institute's website.

SCHEDULE

Name of work : Procurement electrical material - Reg.

S.No	Description	Qty	Units	Rate	Amount
1	Supply and transportation of LED Street light Body made of high grade pressure die – cast Aluminium alloy with corrosion resistant powder coat, having protective toughened glass cover / temperature protective custom molded polycarbonate diffuser, Thermal shock and impact resistant IK07 fixed to the housing by SS screws Suitable lense on LEDs, Less Glare, IP 66 (Silicon gasket ensures Optical & Electrical compartments are IP 66) protected, wide operating voltage range, P.F > 0.90, System having efficacy >120 lumens / watt, with Ingress protection IP66, BIS approved Potted driver, Driver surge protection >10KV, THD70, Inbuilt Electrical protections like Over voltage, short circuit, Over load, Open Circuit, Miswiring, etc complete with BIS certification with 5 years warranty. The contractor has to furnish the manufacturer warranty letter, LM 79 and LM 80 certificates. LUMINAIRE MAKE : PHILIPS / OSRAM / CROMPTON / BAJAJ / Surya / Ecolink / Wipro / Jaquar / Eveready / Halonix / Keselec / HAVELLS / POLYCAB / SURYA / Capart / Fortune Artt / Goldwyn / Panasonic / GM / Goldmedal / Silicon / Orient / HPL / Valmont / Transrail / Bee - Lite / Accent LED MAKE : Philips Lumileds / Cree / Nichia / Osram / Samsung / LG LEDs. (ELEC3.5.1) (f)				
	Street light pole numbers : 05,09,11,13,30, 31,32,35,37,43,44,45,50,51,52,58,70,Near DG quarters,Opp CGG, Krishna Hostel opp,Basket ball court pole, Vivekananda near pole ,Near godavari pole, & manjeera guest house opp -4 90W +/-10% (>=9000 Lumens)	27.00	Nos	5832.00	157464.00
2	Supply and transportation of LED Flood light Luminaire made of pressure die cast aluminum housing with powder coated, having toughened glass cover, Suitable lens on LEDs, IP 66 (Silicon gasket ensures Optical & Electrical compartments are IP 66) protected, wide operating voltage range , P.F > 0.90, System having efficacy >110 lumens/watt, with Ingress protection IP66, Driver surge protection >10KV, THD70, Inbuilt Electrical protections like Over voltage, short circuit, Over load, Open Circuit, Miswiring, etc complete with BIS certification with 5 years warranty. The contractor has to furnish the manufacturer warranty letter, LM 79 and LM 80 certificates. LUMINAIRE MAKE : Philips / Osram / Crompton / Bajaj / Surya / Wipro / Jaquar / Eveready / Halonix / Keselec / Havells / Polycab / Surya / Syska./ Ecolink / Capart / Fortune Artt / GM / Goldmedal / Panasonic / Silicon / Leksa / Orient / HPL / Valmont / Transrail / Bee -Lite/Accent LED MAKE : Philips Lumileds / Cree / Nichia / Osram / Samsung / LG LEDs (ELEC3.5.4) (d)				
	150 W +/-10% (>=13500 Lumens)	4.00	Nos	11218.00	44872.00
3	Supply of PVC / XLPE Insulated Sheathed Multi Core Bright Annealed Bare Copper Conductor Heavy Duty Industrial Cables for Voltage Grade upto 1100 Volts as per IS: 694:2010 including all transportation charges etc complete. Makes : Finolex / RR kabel / Havells / Polycab / RPG / KEI / Gloster / V-Guard / Finecab / SPM / Gemini / Unistar / Windsor / Payal / Fortune Artt / Avocab / Pawancab / Nakoda / HPL / Sudhakar / Bonton / Rajnigandha (ELEC1.5.5) (n)				
	2.5 Sqmm 3 Core	200.00	Mtr	154.00	30800.00
4	Supply of ----- XLPE insulated, 1100V grade armoured aluminium cable with ISI mark as per specification confirming to IS:7098 (Part - I) Makes : Gloster / Finolex / Payal / Beljin / Finecab / RPG / V - Guard / Orbit / Fortune Artt / Gemscab / Bonton / SPM / Unistar / Windsor/ Avocab / Pawancab / Nakoda / Suncab (ELEC4.1.1) (e)				
	10 Sqmm 4 Core	85.00	Mtr	263.00	22355.00
5	Hire for Bucket Ladder vehicle for Street Light Fixing	2.00	LS	8000.00	16000.00
				ECV	271491.00



Dr. MCR HUMAN RESOURCE DEVELOPMENT INSTITUTE OF TELANGANA
GOVERNMENT OF TELANGANA
ROAD No. 25, JUBILEE HILLS, HYDERABAD – 500 033

From
The General Manager (E&F)

To
1.
2.
3.

Lr.No.E1/371/2026, Dt.08.2026

Sub: Dr.MCR HRDIT, Hyd - Engineering Section- Renovation of
Room No.105 in Ground floor of Manjeera Guest House -
Sealed Quotations - Invited -Reg.
&&&

Dr. MCR HRD Institute of Telangana intends to renovate the Room No.105 ground floor of Manjeera Guest House. Hence, sealed quotations are invited from the registered contractors for execution of the work detailed below.

S.No	Name of work	ECV of work (Rs.)	Period for completion of work	Contractor eligible to apply for tender schedules
1	Renovation of Room No.105 in Ground floor of Manjeera Guest House	4,05,795	15 days	Registered Firms /contractors Minimum – Class-V

Date of quotations submission (hard copy): From 01.08.2026 to 03.08.2026 02.00 pm

Date of opening of quotations: 03.08.2026 at 3.30 pm.

Terms & Conditions:

1. The interested agencies shall inspect the work site and acquaint themselves with the scope and nature of the work before submitting their quotations.
2. The agencies shall furnish details of their previous experience in executing similar works, along with supporting documents, including contractor registration, GST registration, PAN, and other relevant statutory documents, with the sealed quotation.
3. Further information and technical details pertaining to the work may be obtained from the Engineering Wing, Office of the Director General, Dr. MCR HRD Institute, Hyderabad, on any working day during office hours.
4. The detailed schedule of quantities/specifications is enclosed herewith.
5. The General Manager (Engineering & Facilities), Dr.MCR HRD Institute, Hyderabad, reserves the right to accept or reject any or all quotations, wholly or partially, without assigning any reason thereof, and the decision of the Institute shall be final and binding.

6. The quotation shall be submitted in a sealed cover, duly super scribed with the following details:


“Quotation for Renovate the Room No.105, ground floor of Manjeera Guest House”

From:

(Name and Address of the Bidder with stamp)

To

The General Manager (E&F),
Dr.MCR HRD Institute of Telangana,
Road No. 25, Jubilee Hills,
Hyderabad – 500033.


General Manager (E&F)

To

The Notice Board at Engg. Wing, 1st floor, Muchukunda Block, Dr.MCR HRDIT,Hyd.
Copy to GM(IT) for uploading the document in the Institute's website.

Name of Work:Repairs and Renovation works like Civil,Sanitary,Furniture & Storage unit and Electrical work at Room No:105,					
SCHEDULE					
Sl.no	Description	Quantity	Units	Rate	Amount
A	Civil Works:				
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including cost and conveyance of all materials to work site and all operational, incidental, labour charges, complete for finished item of work				
2	Providing and applying Wall putty of White Cement or Polymer or Cement based of average 1 to 2 mm thickness over plastered surface to prepare the surface even and smooth after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, applying emery paper, Sand the surface, clean & wipe off loose dust, applying knifing paste filler by putty knife / muslin pad, air dry for 2 - 3 hrs, sand with 180 and 320 No., emery paper for the surface preparation including cost and conveyance of all materials to work site and all operational, incidental, labour charges, complete for finished item of work in all floors for internal walls, including overheads & contractors profit. Except GST.	37.15	Sqm	12.61	468.00
3	Painting to new walls with 2 or more coats of Acrylic Interior emulsion paint of approved brand and shade over a base coat of approved cement primer grade I making making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of work as per SS 912 for external walls for:-External Colouring - Emulsion paint - 2 or more Coats	37.15	Sqm	237.27	8,814.00
8	Polishing to marble flooring where ever required, including cost and conveyance of all materials to site, buffing charges, polishing charges, except GST, etc complete for finished item of work.	235.00	Sqm	249.57	58,649.00
4	Supply & applying Melamine Polish Glossy/ Matt finish to the wood works duly cleaning the surface and applying emery paper, Sand the wood with 180 No., emery paper and then with 320 No., emery paper, clean & wipe off loose dust, applying suitable knifing paste filler / wood filler by putty knife / muslin pad, air dry for 2 - 3 hrs, sand with 180 and 320 No., emery paper, apply two component wood sealer, air dry for 24 hrs, Sand with 320 No emery paper, applying one coat of approved spraying thinner (for spraying)/ applying one coat of approved brushing thinner or general purpose thinner (for brushing) and apply (either with spray or brush) two coats of approved brand melamine including cost & labour charges, emery papers, cost of thinner & melamine polish of approved brands such as Jenson & Nicholson, AsianPaints, Berger Paints or equivalent etc., complete for finished item of work	55.22	Sqm	501.90	27,715.00
5	Supply,Fixing and Installation of Dual Roller - Zebra Blinds of Roller Blinds of approved colour and shade as per by Engineer in Charge and mounting brackets,Side action control unit locks into brackets, 4.5mm diameter with connector Extruded PVC bottom bar in UPVC with 4locking channels for fabrics & trims,Aluminium anodized bottom bar profile with color matched end caps and 29 x 19mm with fabric locking slot,Co-ordinating end caps allows quick and easy mounting in either top fix or face position,operating chain is designed to provide a smooth operation,including cost and conveyance of all materials to site, labour charges, overheads & contractors profit etc., all taxes, except GST complete for finished item of work.	15.00	Sqm	173.96	2,609.00
		9.06	Sqm	2152.00	19,497.00

6	Supply,Providing, Making Hand Wash Granite Counter of Length 600m x Width 500 mm and 750 mm Height by using with High Polished Granite 16 to 18 mm thick up to 8'-00 (2.43 M) with using in single piece with with edges rounded,With 2 Nos Vertical Support using with Each Support with 2 Nos of size 500 Width x750mm Height, set over with full depth jointing flooring for grout/synthetic/resin based adhesive in 3-5 mm thick ,of approved make and as per approved drawing by Engineer in charge, including necessary hardwares,Synthetic adhesive (Resin + Hardener),all labour charges, all incidental and operational charges, Transportation, labour charges, overhead charges & contractor profit , all taxes excluding GST etc., complete as directed by Engineer In Charge for finished item of work	1.00	Units	6411.33	6,411.00
7	Supplying and fixing Gyp board suspended regular single layer false ceiling (GS - MFSC-4.1 as per India Gypsum) using 12.5mm thick Gypboard conforming to IS 2095 - 1982 fixing of Gyp Steel GI perimeter channels of size 20mm x 27 mm x30mm (web) of 0.55 mm thick along with perimeter of ceiling screw fixed to brick work/ partition at 610mm c/c and suspending the frame work using intermediate channels (45mm x15mm x15mm x0.9 mm) from soffit at 1220 mm c/c with ceiling angle (25mmx10mm x0.55mm) fixed with GI cleat and steel expansion fastners and connecting clip to the ceiling fan (with knurled web of 1.5mmX26mm x 10.5mm x 0.55mm) fixed in direction perpendicular to the Intermediate channel at 457mm c/c and fixing the 12.5mm tapered edge Gypboard with 25mm dry wall screws at 230 mm c/c & jointing and finishing using joint compound and paper tape to have a flush look including filling the tapered and square edges with jointing compound , two coats of dry wall top coat,as per approved drawing by Engineer in charge, including all incidental and operational charges, Transportation ,labour charges, overhead charges & contractor profit , all taxes excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and at all levels .	0.00	Sqm	1300.39	-
Civil Works-A					1,24,163.00
9	Supply,Providing, Making Crockery Storage Unit of size: 620 L X 560 W X 2100 Ht,using with 19 mm thick Plywood of BWR Grade conforming to IS:303 BWR Grade for Outer Horizontal, vertical,Top and Bottom of the storage unit and vertical intermediate member and Horizontal Members and Door shutters Using 19 mm thick plywood,Top & Bottom Member of size 620x560 mm,Sides face 2 Nos of size :560x2100 mm and 1 Nos of Intermediate vertical member of size:560x1350 mm,3 Nos of Intermediate Horizontal member of size:560x600 mm, 2 Nos of Door shutter of size : 310x1350 mm and 2 Nos of Door Shutter of Size: 320x750 mm and Exposed surface and Internal surfaces of the storage,Draw unit and Door shutters is finished with Melamine Laminate Sheets - Mat Finish: 1.00 mm thick of approved colour or pattern as per approved drawing as directed by Engineer-in-Charge,8 Nos of Doors with Clip on 3D Adjustable Hinge of Code STHOC of Dorset for each shutter 2 nos , 8 Nos of Stainless Steel Door Handles 125 mm Long for each door 1 No,Magnetic Catcher for Each Door, Lock set,of approved make and as per approved drawing by Engineer in charge, including necessary hardwares,Adhesive compound,nails /self driving screws,all labour charges, all incidental and operational charges, Transportation, labour charges, overhead charges & contractor profit , all taxes excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and at all levels .	1.00	Unit	26883.84	26,884.00

10	Supply,Providing, Making Wardrobe Storage Unit of size: 1050 L X 550 W X 2100 Ht,using with 19 mm thick Plywood of BWR Grade conforming to IS:303 BWR Grade for Outer Horizontal, vertical,Top and Bottom of the storage unit and vertical intermediate member and Horizontal Members and Door shutters Using 19 mm thick plywood,Top & Bottom Member of size 1050x550 mm,Sides face 2 Nos of size :550x2100 mm and 1 Nos of Intermediate vertical member of size:550x2060 mm,2 Nos of Intermediate Horizontal memeber of size:1050x560 mm, 3 Nos of Door shutter of size : 350x2100 mm Exposed surface and Internal surfaces of the storage,Draw unit and Door shutters is finished with Melamine Laminate Sheets - Mat Finish: 1.00 mm thick of approved colour or pattern as per approved drawing as directed by Engineer-in-Charge,3 Nos of Doors with Clip on 3D Adjustable Hinge of Code STHOC of Dorset for each shutter 3 nos , 3 Nos of Stainless Steel Door Handles 125 mm Long for each door 1 No,Magnetic Catcher for Each Door, Lock set,of approved make and as per approved drawing by Engineer in charge, including necessary hardwares,Adhesive compound,nails /self driving screws,all labour charges, all incidental and operational charges, Transportation, labour charges, overhead charges & contractor profit , all taxes excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and at all levels .	0.00	Unit	41312.26	-
11	Supplyand installation of Compact Wooden Desk of Size:L 1200 X D 600 X Ht 740 mm,Desk with an Built lockable drawer and an integrated one hinge door pedestal for storage ,as per approved drawing colour and shade by Engineer in charge, including all incidental and operational charges, transportation, labourcharges, and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work.(Make:Godrej/Equivalent)	1.00	Each	10000.00	10,000.00
12	Supply and installation of Greta Medium Back Mesh Chair,Single Lock Synchro Mechanism,adjustable lumbar support with one way adjustable armrests(Height) and nylon base ,Fabric Upholstered Cushion Seat & back,as per approved drawing colour and shade by Engineer in charge, including all incidental and operational charges, Transportation ,labour charges, and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and at all levels.(Make:Godrej/Equivalent)	1.00	Each	5000.00	5,000.00
13	Supply and installation of Compact soft lounge seating with stylish straight wooden legs, perfect for cozy spaces,Seat Upholstery Fabric,Understructure Beach Wood,as per approved drawing colour and shade by Engineer in charge, including all incidental and operational charges, Transportation ,labour charges, and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and at all levels.	2.00	Each	3000.00	6,000.00
14	Supply and installation of Pod Table of Size:800 mm Dia ,Ht:743 mm with SS Legs,as per approved drawing colour and shade by Engineer in charge, including all incidental and operational charges, Transportation ,labour charges, and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and at all levels.	1.00	Each	25300.00	
15	LS Provision for repairs to existing wardrobe, cot, supply of two tables beside cot, Iron pressing table repair, replacement of cloth to existing chair cushions			LS	75,000.00
Furniture & Storage Unit-B					1,22,884.00
Sanitary Items					

15	Supply, Installation and commissioning approved make floor mounted Close Coupled wash down EWC conforming to IS:2556 (Part 8)-2004 suit with 'P' trap with dual flush porcelain cistern fixed on wash down EWC with all internal parts of dual flush cistern, ultra solid seat cover of approved make with rubber buffer and cap & 15 mm angle stop cock & 450 mm long PVC inter connection pipe wall flanges all of approved make etc. all of approved make, as per approved drawing by Engineer in charge, including all incidental and operational charges, transportation, labour charges and all taxes except GST etc., complete as directed by Engineer In Charge for finished item of work	1.00	Each	16032.60	16,032.60
16	Supply & Fixing of Chromium plated finish brass body quarterturn Bibcock cum Health Faucet with 1m long tube and wall hook, including all incidental and operational charges, transportation, labour charges and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels	1.00	Each	3675.00	3,675.00
17	Supplying & Fixing of Counter Top Wash Basin of Size: 495x395x150 mm, Thin Rim Table Top Basin, Shape - Rectangular and Model JDS-WHT-25909, as per approved drawing by Engineer in charge, including all incidental and operational charges, Transportation, labour charges and all taxes except GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels.	1.00	Each	5258.80	5,258.80
18	Supply and Fixing of 15 mm brass body Premium variety Chromium plated finish long neck pillar cock with aerator of not less than 500 grams weight quarter turn spindle conforming to IS 8931 and with CP screws etc., complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	1312.20	1,312.20
19	Supply and Fixing of 15 mm CP finish brass body wall mixer conforming to IS 8931 with center distance 150 mm conforming to IS 8931, complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	2455.00	2,455.00
20	Supply and Fixing of 15 mm nominal size CP finish brass over head shower arm of 450 mm long with 90 degree bend & wall flange suitable for rain shower, complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	1409.00	1,409.00
21	Supply and Fixing Chromium plated finish stainless steel body Towel Ring with CP screws etc., complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	1148.00	1,148.00
22	Supply and Fixing Chromium plated finish CP finish steel towel rod of 600 mm long and 20 mm dia with brackets etc., complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	456.00	456.00
23	Supply and Fixing of Chromium plated finish stainless steel body Toilet paper holder, including all incidental and operational charges, transportation, labour charges and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels	1.00	Each	1001.00	1,001.00

24	Supply and Fixing of Stainless steel 4" dia round Grating with frame for nahany or floor trap cover,including all incidental and operational charges, transportation ,labour charges and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels	1.00	Each	75.00	75.00
25	Supply and Fixing of Double coat hook,including all incidental and operational charges, transportation ,labour charges and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels	1.00	Each	859.00	859.00
26	Supply and Fixing of brass soap dish with accessories,including all incidental and operational charges, transportation ,labour charges and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels	1.00	Each	650.00	650.00
27	Supply and Fixing Stainless steel liquid soap container wall mounted and bottle type, including all incidental and operational charges, transportation ,labour charges and all taxes Excluding GST etc., complete as directed by Engineer In Charge for finished item of work for all floors and all levels	1.00	Each	518.00	518.00
28	Supply and Fixing of 15 mm nominal size CP finish brass angled stop valve screw type with internal /external threaded conforming to IS 8931 with CP screws etc., complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	273.00	273.00
29	Supply and Fixing of Swivel Mirror of Model No:ACN-1195 , screws etc., complete including cost and conveyance of all materials, labour charges for fixing, etc overheads & contractors profit, all taxes, except GST, complete for finished item of work in all floors	1.00	Each	3050.00	3,050.00
Sanitary Items -C					38,172.60
B	Electrical Items				
1	Supply and fixing of following size medium/heavy grade, FRLS with IS:9537 part 3 regid PVC pipe with junction boxes, bends etc, including labour charges for fixing the pipe with all accessories etc., complete.,the cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. The work is to be carried out as per the specifications and requirement of site conditions under the guidance of Engineer-In-Charge.Makes : Sudhakar / Finolex / Modi /Polycab				
	a) 25mm dia heavy grade PVC pipe	0.00	Rmt	111.00	-
2	Point Wiring with three runs of 1.5 Sqm FRLS PVC insulated flexbile copper conductor cable as Phase ,neutral and earthing in the existing PVC conduct pipe with 6A modular type switch with PVC module front plate and including all labour charges etc., complete for light point, fan point, call bell point and exhaust fan points etc complete.The cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work Makes : Finolex / RR kabel / Havells /Polycab Makes of Switches : Makes : Legrand Myrius / GM Four Five / Goldmedal Curve / Anchor Roma violaz				
a	1 LP Controlled by 1 Switch	0.00	Each	918.00	-
b	2 LP Controlled by 1 Switch	0.00	Each	1070.00	-

3	Supply and laying of 3 runs of 56/0.3mm (4 Sqmm) PVC FRLS insulated flexible Copper cable and laying the cable in the existing pipe including all labour charges etc., complete for Switch board mains and independent Raw/UPS Power Sockets Wiring) the cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. Makes : Finolex / RR kabel / Havells / Polycab / RPG / KEI / Gloster / V-Guard	25.00	Rmt	234.00	5,850.00
4	Supply, Installation, Testing & Commissioning of 1 nos 16/20A 3/5 pin modular socket and 1 nos 16/20A modular switch with front plate as directed by the dept. The cost including all incidental and operational charges, labour charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. The work is to be carried out as per the all specifications and requirement of site conditions under the guidance of Engineer-In-Charge . Make: Legrand Myrius/ gold medal	0.00	Each	968.00	-
5	Supply and Installation, Testing & Commissioning of 2 No 3/5 pin 16A modular socket with 2 No 16A modular switch, 6 modular GI / PVC back box along with front plate as directed by the Dept. the cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. Makes : Legrand or equivalent	0.00	Each	1258.00	-
6	Supply, Installation, Testing and Commissioning of 18 W +/-10% (≥ 1800 Lumens) back lit LED Down Light Recessed / Surfacemounting round / square with housing made of Powder coated Pressure die cast aluminium housing with extended heat sink, with Protruded high efficiency diffuser, IP20, with wide operating voltage range, Power factor > 0.9 , Surge protection: $> 2KV$, System efficacy of > 100 lumens/watt, CCT: 3000K - 6500K as desired by the department and as per IS, CRI > 80 , and THD is less than 15% etc., complete with 5 years warranty with BIS Certification. LUMINAIRE MAKE : Phillips / OSRAM / Wipro / Crompton / Bajaj / Havells / Jaquar / Panasonic / Halonix / HPL / Eveready / Surya / Keselec / Arraystorm / GM / Goldmedal / Goldwyn / Fortune Art / Lighting Technologies LED MAKE : PHILIPS LUMILEDS / CREE / NICHIA / OSRAM / SAMSUNG / LG LEDs. The cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. The work is to be carried out as per the specifications and requirement of site conditions under the guidance of Engineer-In-Charge. LUMINAIRE MAKE : Phillips / OSRAM / Wipro / Crompton / Bajaj / Havells.	10.00	Each	500.00	5,000.00
7	Supply, Installation, Testing and Commissioning of wall suitable for erection Supply of 12" (300mm) Light duty exhaust fan with metallic blades etc complete, the cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. The work is to be carried out as per the specifications and requirement of site conditions under the guidance of Engineer-In-Charge. Make: Crompton or equivalent	1.00	Each	2319.00	2,319.00
8	Supply, installation, testing Providing 2 runs of Copper tubes for suction and liquid between indoor and outdoor unit for split / Casseeete Air Conditioner including foaming etc., complete. 1. 3/4" x 3/8" 2. 5/8" x 1/4" 3. 1/2" x 1/4" or equivalent sizes	15.00	Rmt	1040.00	15,600.00
9	Supply, Fabrication of 1 set MS bracket suitable for fixing out door unit of split AC unit.	2.00	Set	1008.00	2,016.00

10	Supply, installation, testing and Transportation of 1.5 TR 3 Star of INVERTER Model Cool type split AC unit with high wall mounted Single Split 100% copper indoor and outdoor condensing unit Hermetically sealed compressor suitable for operation on 230V, 50Hz, 1Phase AC supply capable of performing Heat cool dehumidifying air circulating and filtering with cooling and condensing units with 3.0 mts of copper piping, insulation kit and 4 mts of 4 core copper flexible chord (Voltage range 160- 264 volts) and cordless remote control with warranty of compressor for 5 years and comprehensive maintenance for 2 years . The cost including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work. The work is to be carried out as per the specifications and requirement of site conditions under the guidance of Engineer-In-Charge. Makes : Daikin / Blue Star / Toshiba / Carrier / Hitachi or equivalent	2.00	Each	36910.00	73,820.00
11	Supply, Transportation, Installation, Testing and commissioning of storage / Pressure type Vertical / Horizontal 230/250V single phase 2000 watts 5 Star rated water heater with ABS plastic body of 10 Litres capacity to withstand up to 8.0 bar of water pressure including all standard accessories and dead weight pressure reducing valve on out let side, including cost of 2 Nos SS flexible braided hose pipe, testing and all labour charges etc., complete. Makes : Crompton / Jaquar / Venus / Racold / AO Smith / Goldmedal / GM / Havells / Bajaj / Hindware / Anchor Panasonic or equivalent including all incidental and operational charges, labour charges, seigniorage charges, cost and conveyance of all materials etc excluding GST, complete for finished item of work.	1.00	Each	9800.00	9,800.00
12	Supply, Transportation of energy efficient fan, 1200 mm sweep, aluminium body, consuming 28 W, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) motor, class of insulation: F, 3 no's blades, 30 cm long down rod, 2 no's canopies, shackle kit, copper winding, Power Factor greater than 0.90, Service Value (CMMAV) greater than 8.0, Air delivery minimum 235 CMM, 350 RPM(tolerance as per IS:374-2019), THD less than 10%, Surge Protection 6 KV with remote or compatible to electronic step type regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75°C(max), insulation resistance more than 2 mega ohm, suitable for 230V, 50 HZ, single phase AC supply, earthing etc., including all standard accessories etc., complete with 5 years warranty. Makes : Atomberg (Efficio) / Havells / Bajaj / Orient / Halonix / Crompton / Goldmedal / GM.	2.00	Each	3085	6,170.00
Electrical Items-D					1,20,575.00
Grand Total (A+B+C+D)					4,05,795.00