



Dr. MCR HUMAN RESOURCE DEVELOPMENT INSTITUTE OF TELANGANA
GOVERNMENT OF TELANGANA
ROAD No. 25, JUBILEE HILLS, HYDERABAD – 500 033

From
The General Manager (E&F)

To
1.
2.
3.

Lr.No.E1/201/2026, Dt.19.06.2026

Sub: Dr.MCR HRDIT - Engineering Section- Repairs and to kerb walls
along the internal roads in the Institute campus - Sealed
Quotations - Invited -Reg.
&&&

Dr. MCR HRD Institute of Telangana intends to take up the repairs to the kerb walls along the internal roads in the Institute campus. Hence, sealed quotations are invited from the registered contractors for execution of the work detailed below.

S.No	Name of work	ECV of work (Rs.)	Period for completion of work	Contractor eligible to apply for tender schedules
1	Repairs and to kerb walls along the internal roads in the Institute campus	3,03,713	15 days	Registered Firms /contractors

Date of quotations submission (hard copy): From 30.06.2026 to 04.07.2026 at 02.00 pm

Date of opening of quotations: 04.07.2026 at 3.30 pm.


Terms & Conditions:


1. The interested agencies shall inspect the work site and acquaint themselves with the scope and nature of the work before submitting their quotations.
2. The agencies shall furnish details of their previous experience in executing similar works, along with supporting documents, wherever applicable.
3. Further information and technical details pertaining to the work may be obtained from the Engineering Wing, Office of the Director General, Dr. MCR HRD Institute, Hyderabad, on any working day during office hours.
4. The detailed schedule of quantities/specifications is enclosed herewith.
5. The General Manager (Engineering & Facilities), Dr.MCR HRD Institute, Hyderabad, reserves the right to accept or reject any or all quotations, wholly or partially, without assigning any reason thereof, and the decision of the Institute shall be final and binding.
6. The quotation shall be submitted in a sealed cover, duly super scribed with the following details:

"Quotation for "Repairs and to kerb walls along the internal roads in the Institute campus"

From:
(Name and Address of the Bidder with stamp)

To
The General Manager (E&F),
Dr.MCR HRD Institute of Telangana,
Road No. 25, Jubilee Hills,
Hyderabad – 500033.


General Manager (E&F)



To
The Notice Board at Engg. Wing, 1st floor, Muchukunda Block, Dr.MCR HRDIT,Hyd.
Copy to GM(IT) for uploading the document in the Institute's website.

SCHEDULE

S.No	Descriphon	Nos	L	i	»	i	Qty	Unlts	Rate	Total
1	Painting to new walls with 2 coats of ready mixed OIL BASED EMANEL PAINTS distemper of approved brand and shade over a base coat of primer of Interior grade I of approved brand, making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of Work as per SS 911 for internal walls. Excluding taxes like GST.									
							1143.00	Sqm	181.20	207111.6
	Plastering to ceiling with 12mm thick single coat in CM (1:3) dubara sponge finish including cost and conveyance of all materials and labour charges, all operational, incidental such as scaffolding charges, lift charges, including cutting of Grooves, finishing, curing, over heads & contractor profit, but excluding seignorage charges and taxes like GST, etc., complete for finished item of work. (APSS 901 & 903) (CSSR).									
							285.75	Sqm	245.84	70248.78
3	Supply and placing of Design Mix Concrete M 20 grade corresponding to IS 456 with minimum cement content of 330 kgs per 1 cum of concrete using WBGH BATCHER / NIXER with 20mm size graded machine crushed hard Granite metal (coarse aggregate) (consisting of nominal size metal 60% of 20mm, 15% of 13.20/12.50mm, 15% of 10mm and 10% of 6mm) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) (with 50% river sand & 50% manufactured sand) coarse aggregate, water etc., to site, centering using scaffolding pipes, etc., including all operational, incidental and labour charges such as weigh batching, Hand mixing, laying concrete, curing and cost of etc. complete but excluding cost of steel and its fabrication charges for									
		9Nor	9.75	0.30	0.15		3.949			
		rnos	2.	0.30	0.1		0.109			
							4.06	Cum	6494.00	26353.30
	ECV									303713.68

12

2. heads / and
4/5/26